



# TPO M CONTROL UNIT



SKIOLD MAKES THE DIFFERENCE!

All measures in mm.

Operating Voltage	3 x 400 V + N + PE
Prefuse	Min. 10 amp.. - max. 25 amp
Alarm output	Yes
Stop System	Capacitive, 230 VAC with relay output Adjustable key distance 4-12mm Adjustable timer (delayed on release) 1 sec. - 10 min.
Stop system for hopper /flex auger	Capacitive 230 VAC with relay output Adjustable key distance 4-12mm Adjustable timer (delayed on operate) 1 sec. - 10 min.
Function	Main switch on front Start,stop and reset on front Adjustable sensor cancel time up on start Adjustable max. running time Start on 24 hour clock

Item number	Description
140 601 001 800	Control unit TPO M 0,75kW
140 601 001 810	Control unit TPO M 0,75kW/0,09kW
140 601 001 820	Control unit TPO M 0,75kW/0,75kW
140 601 001 801	Control unit TPO M 1,1kW
140 601 001 811	Control unit TPO M 1,1kW/0,25kW
140 601 001 821	Control unit TPO M 1,1kW/0,75kW

